

Ensure that power to unit is off. Splice supply wires with receptacles. Replace wired receptacle plate and fasten in place. Mount finished cast alum. cover set to housing using (4) factory supplied stainless steel 8-32 X 1-1/4" flat head phillips m./ screws.

